



1. THE CONTRACTOR SHALL SUPPLY PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE WORK SHOWN. ANY DISCREPANCIES BETWEEN QUANTITIES SHOWN ON THE PLANT SCHEDULE AND THOSE REQUIRED BY THE CONTRACT DRAWINGS SHALL NOT ENTITLE THE CONTRACTOR TO ADDITIONAL REMUNERATION – ALL PROPOSED PLANTINGS ARE NATIVE STRAIGHT SPECIES.
2. THE CONTRACTOR SHALL VERIFY AND VISUALLY INSPECT FINAL SELECTION OF PLANT MATERIALS WITH THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
3. ALL PLANTING LOCATIONS SHALL BE STAKED OUT AND APPROVED IN THE FIELD BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
4. NO PLANT MATERIAL WILL BE ACCEPTED WHICH DISPLAYS MAJOR IRREGULARITIES OR MECHANICAL DAMAGE. THE OWNER RETAINS THE RIGHT TO REJECT ANY PLANT MATERIAL DEEMED UNFIT.
5. NO PLANT MATERIAL SUBSTITUTIONS SHALL TAKE PLACE WITHOUT THE APPROVAL OF THE TOWN OF HINGHAM CONSERVATION COMMISSION..
6. EXISTING VEGETATION SHALL REMAIN UNDISTURBED IN ALL AREAS WHICH ARE NOT PART OF THE PROPOSED CONTRACT LIMIT LINE.
7. GUARANTEE:
 - FOR A PERIOD OF TWENTY FOUR MONTHS FROM THE DATE THAT THE WORK UNDER THIS CONTRACT IS CERTIFIED AS COMPLETE, THE CONTRACTOR SHALL: 1) GUARANTEE ALL PLANTS AND SEEDED AREAS UNDER THIS CONTRACT; 2) REMOVE AND REPLACE DURING THIS GUARANTEE PERIOD PLANTS WHICH DIE OR ARE IN A BADLY IMPAIRED CONDITION; 3) REPLANT WITH STOCK OF SAME SIZE AND QUALITY AS ORIGINALLY SPECIFIED; 4) GUY AND MAINTAIN AS SPECIFIED HEREIN AT NO ADDITIONAL COST TO THE OWNER. 5) WATER AS NEEDED DURING THE GUARANTEE PERIOD.
 - A. REPLACEMENTS MADE WITHIN SIX MONTHS AFTER THE BEGINNING OF THE GUARANTEE PERIOD SHALL NOT EXTEND THE GUARANTEE PERIOD OF THESE PARTICULAR PLANTS. THOSE REPLACEMENTS MADE SIX MONTHS OR MORE AFTER THE BEGINNING OF THE GUARANTEE PERIOD SHALL BE MAINTAINED AND GUARANTEED FOR A PERIOD OF SIX MONTHS FROM THE TIME OF PLACEMENT.
8. APPLY MULCH AND WATER THOROUGHLY DURING AND IMMEDIATELY AFTER PLANTING.
9. ALL PLANTINGS WITHIN BUFFER ZONES SHALL ADHERE TO THE TOWN OF HINGHAM CONSERVATION COMMISSION BUFFER ZONE MITIGATION POLICY.

PLANT SCHEDULE						
SYMBOL	#	KEY	BOTANICAL NAME	COMMON NAME	SIZE/ROOT	NOTES
TREES						
	5	AR	Acer rubrum	RED MAPLE	3" CAL. B&B	
	4	NS	Nyssa sylvatica	BLACK TUPELO	3" CAL. B&B	BUFFER PLANTING (1)
	3	QA	Ulmus americana	AMERICAN ELM	3" CAL. B&B	BUFFER PLANTING
SHRUBS						
	6	CA	Cornus amomon	SILY DOGWOOD	24–36" HT.	BUFFER PLANTING
	6	IG	ilex glabra	INKBERRY	24–36" HT.	BUFFER PLANTING
	8	VD	Viburnum dentatum	ARROWWOOD DOGWOOD	24–36" HT.	BUFFER PLANTING
SEED MIXES						
		SM1	NEW ENGLAND CONSERVATION MIX, PRODUCED BY NEW ENGLAND WETLAND PLANTS, INC. 25 LB/ ACRE.			
		SM2	NEW ENGLAND EROSION CONTROL, PRODUCED BY NEW ENGLAND WETLAND PLANTS, INC. 35 LB/ ACRE.			
			BUFFER ZONE/RA RESTORATION AREA (7,601 S.F.)			

TREE TABLE			
TREES TO BE REMOVED	EXISTING	REQUIRED REPLACEMENTS	PROPOSED REPLACEMENTS
WITHIN THE 50-100" BUFFER:	0	ONE TO ONE TREE REPLACEMENT (0)	4
WITHIN THE 0-50" BUFFER:	3 - TWO(2) 6" CAL. HONEYLOCUST & ONE (1) 7" SLIPPERY ELM	TWO TO ONE TREE REPLACEMENT (6)	3
OUTSIDE THE 100" BUFFER:	15 - FIVE (5) GREATER THAN 6" CAL.	-	5
TOTAL	18	6	12

TOPSOIL AND SEED ALL DISTURBED LAWN
AREAS OUTSIDE SEED MIX AREAS, TYPICAL
UNLESS NOTED OTHERWISE

